



Specification for accessories				
No.	Description	Name	Milling by Staticus	Mounting
1	Lock A (day lock)	ASSA 732-50	Yes	Factory
2	Striker plate	Step ST600	Yes	Factory
3	Main preload electromagnetic strike	-	-	-
4	Main cylinder	ASSA 2356	Yes	Factory
5	Handle/Pull handle	-	-	-
6	Plate for main handle	-	-	-
7	Pull handle	Diamantek Classic K3-1400/38	Yes	Factory
8	Additional lock	ASSA 411	Yes	Site
9	Additional striker plate	ASSA 1487-9	Yes	Site
10	Additional cylinder	-	-	-
11	Additional handle	-	-	-
12	Plate for additional handle	-	-	-
13	Antipanic handle	ASSA 179B	Yes	Factory
14	Doors closer (automatic)	-	-	-
15	Doors closer (secondary)	Dorma ED 250 HE	Yes	Factory
16	Accessories for closer	-	-	-
17	Door closer coordinator	-	-	-
18	Closer sensors and actuators (radars)	-	-	-
19	Closer pressing sensor	-	-	-
20	Cover for wire	Roca 5210	Yes	Factory
21	Signalization magnets	DC1076-6M	Yes	Factory
22	Glass break detectors	Q 00454	No	Site
23	Door automatics	-	-	-
24	Card reader	-	-	-
25	Protective device	Prosecure Opti Safe 750-2	Yes	Factory
26	Blind post	ASSA 225x22	Yes	Site
S1	Hinges	239603	Yes	Factory

Product name: UGP21-1.1h

Position	Description
Quantity	2 pcs.
Profile system	Shuco AWS 75.SI+/ADS 75.SI
Frame width	1109 mm (milled 1088mm)
Frame height	2200 mm
Profile colour inside	RAL 7015 gloss 30%
Profile colour outside	RAL 7015 gloss 30%
Glazing/Filling	57 mm
Leaf opening type	Outward
Dim. from FFL to main lock center	1100 mm
Free opening width	855 mm
Threshold	381160
Security class	RC3

Responsible department	Project manager	Prepared	Approved			
Design depart.	Renata Visockaitė	Daniil Kac	Martynas Seliuta			
Owner	STATICUS STATICUS, UAB Alkskalo Nr. 5212 Tel. (370) 5 2398877 Fax. (370) 5 2398880, e-mail: info@staticus.com, www.staticus.com	Document type	Document status			
		Technical drawing	Completed			
			Title		Document number	
			Doors UGP21-1.1h Level 11	F-40-6-5019.1		
Project title			Revision	Date	Scale	Page
20002_SL_Skalen			0	2021.12.12	1:20	1/1