


Specification for accessories				
No.	Description	Name	Milling by Staticus	Mounting
1	Lock A (day lock)	ASSA 732-50	Yes	Factory
2	Striker plate	Step ST600	Yes	Factory
3	Main preload electromagnetic strike	-	-	-
4	Main cylinder	ASSA 2356	Yes	Factory
5	Handle/Pull handle	-	-	-
6	Plate for main handle	-	-	-
7	Pull handle	Diamantek Classic K3-1400/38	Yes	Factory
8	Additional lock	ASSA 411-50	Yes	Factory
9	Additional striker plate	ASSA 1487-9	Yes	Factory
10	Additional cylinder	ASSA 3212	Yes	Factory
11	Additional handle	-	-	-
12	Plate for additional handle	-	-	-
13	Antipanic handle	-	-	-
14	Doors closer (automatic)	-	-	-
15	Doors closer (secondary)	Dorma TS 98 XEA	Yes	Factory
16	Accessories for closer	-	-	-
17	Door closer coordinator	-	-	-
18	Closer sensors and actuators (radars)	-	-	-
19	Closer pressing sensor	-	-	-
20	Cover for wire	Roca 5210	Yes	Factory
21	Signalization magnets	DC1076-6M	Yes	Factory
22	Glass break detectors	Q 00454	No	Site
23	Door automatics	-	-	-
24	Card reader	-	-	-
25	Protective device	-	-	-
26	Blind post	-	-	-
S1	Hinges	239871	Yes	Factory

Product name: UGP06-1.1h

Position	Description
Quantity	1 pcs.
Profile system	Shuco AWS 75.SI+/ADS 75.SI
Frame width	1415 mm
Frame height	2310 mm
Profile colour inside	RAL 7015 gloss 30%
Profile colour outside	RAL 7015 gloss 30%
Glazing/Filling	57 mm
Leaf opening type	Outward
Dim. from FFL to main lock center	1100 mm
Free opening width	1000 mm
Threshold	381160
Security class	RC3

Responsible department	Project manager	Prepared	Approved			
Design depart.	Renata Visockaitė	Daniil Kac	Martynas Selietu			
Owner	STATISTIC STATISTICS, UAB Ateklato Nr. 512 Tel. (010 5 298877) Fax: (010 5 298800, e-mail: info@statistic.com, www.statistic.com		Document type	Document status		
			Technical drawing	Completed		
Project title	20002_SL_Skalen		Title	Document number		
			Doors UGP06-1.1h Level 11	F-40-6-5021.1		
			Revision	Date	Scale	Page
			0	2021.12.12	1:20	1/1