



TECHNICAL DESCRIPTION

CRAMO SITE HUTS 1.0





General

EXTERNAL DIMENSIONS L x W x H	8,60 x 3,00 x 3,00 m
INTERNAL DIMENSIONS L x W x H	8,10 x 2,60 x 2,40 m
THERMAL PERFORMANCE	
FLOOR	U = 0,27 W/(m ² ·K)
WALLS	U = 0,37 W/(m ² ·K)
ROOF	U = 0,33 W/(m ² ·K)

Confirmed product

Confirmed supplier

STRUCTURE		
BASE FRAME	Steel, RAL 9005	
FRAMEWORK	Timber	
INSULATION	Glass wool KL-37 (λ=0,037 W/mK)	
EXTERIOR		
WALL FINISH STANDARD UNITS	Wooden siding NCS S 5000-N	
WALL FINISH INDUSTRY UNITS	Wooden siding RAL 7031	
MOULDINGS STANDARD UNITS	Wooden, RAL 3000	
MOULDINGS INDUSTRY UNITS	Wooden, RAL 7031	
ROOFING	Protan 1,2mm, light grey F 91	
INTERIOR		
FLOORING	PVC 1,5mm, Tarkett Optima 825 (turned up on the wall 100mm)	
WALL PANEL DRY ROOMS	Forestia One-Step 030 Perlegrå	
WALL PANEL WET ROOMS	Flex Plywood 02 PP RAL 9016	
WALL PANEL SHOWER AREA	Fibo Wallpanel 110 S white	
CEILING PANEL	Forestia One-Step 14TFL	
MOULDINGS OFFICE UNITS	Beech, mdf	
MOULDINGS SANITARY/LABOUR UNITS	White, wooden	
WINDOWS AND DOORS		
WINDOWS	White PVC, outward opening	
INTERNAL DOORS	Swedish standard; white/beechn	
EXTERNAL DOORS	Wooden, RAL 3000	
INSTALLATIONS		
ELECTRICITY	Lead-in terminal box 32 A	El-Börn AB
LUMINAIRES	LED, with sensors	Amiga AB
HEATING	Front convectors Nobo	Amiga AB
VENTILATION OFFICE UNITS	Heat exchanger Mitsubishi VL-100	
VENTILATION SANITARY/LABOUR UNITS	S&P Silent ventilator	
	Fresh air valves	



WATER AND SEWAGE

WATER PIPES

WATER MIXERS

WC BOWLS

WASH BASINS

WATER HEATING

FLOOR DRAINS

WATER AND SEWAGE COUPLING

EQUIPMENT

FRIDGES

DISHWASHER

MICROWAVE

DRYING CABINETS

DOUBLE LOCKERS, WITH BENCH

ROOF DRAINAGE

RAIN GUTTERS; DRAINPIPES

LIFTING AND STACKING

LIFTING

STACKING

Visible piping

Oras

Gustavsberg Nautic, single flush

Jika Zeta 40

Nibe electric water heaters

Jafo

Automatic coupling box
(sewage Ø110; water ¾")

Exquisit KS350-4A++, white

Exquisit KS 17-1 RV A++, white

Helkama HAP6003

Exquisit MW802G, white

Nimo Easy Dryer 1900, white

UGAB , Dryin Cabinet Pro 21x6x11,5

1795x600x800, RAL 7035/5024

Hot-galvanized steel

Crane; forklift

2 storeys