



EXTERIOR WALL CONSTRUCTION	
- Spruce shingles, 3 layers	18mm
- Insect mesh	
- Plywood (C250) batten hor.	9mm
- Plywood (C250) ventilation slats	9mm
- Plywood (C250) ventilation slats	9mm
- Vapor permeable underlay membrane	
- Gluelaminated frame s480mm	50mm
- Polyurethane (closed cell), 50mm	
- Plywood battens hor.	9mm
- Diffusion membrane	
- Wall paneling (aspen/spruce)	12mm

FLOOR CONSTRUCTION	
- Floorboard	28mm
- Wooden floor frame (C24)	95mm
- Impregnated timber frame	90mm

SECTION A 1:40

 IGLUCRAFT	Project	CO-02542	Drawing nr.	KJ-03	Rev.	-
	Model ID	CUSTOM DESIGN IGLUSAUNA				
	Drawing	SECTION A	Scale	1:40	Date	14/06/2024